

Duct AC Technical specification



U-Match Air Conditioner Indoor Unit

Parameter(Unit)			Value	
Type			Duct	
Model			UADG36H	
Code			CF022N2700	
Electrical Data	Power supply		V-Hz-Ph	220-240-50/60-1
	Power input <sup>1</sup>	Cooling	kW	0.20
		Heating	kW	0.20
	Input current <sup>1</sup>	Cooling	A	0.91
		Heating	A	0.91
	Max. Overcurrent Protection		A	/
	Min/Max Voltage	Min/Max Voltage (V)	V	198/264
Power cord spec	Electrical Conduit Size (Inch)	mm <sup>2</sup> xpcs	1.00×3	
Fuse (A)			A	3.15
Sound Pressure Level (SS/H/M/L)*			dB (A)	43/42/41/39
Sound Power Level (SS/H/M/L)*			dB (A)	53
Refrigerant	Type		—	R410A
	Control		—	/
Air Flow Volume(rated EXP)			CFM	1177
			m <sup>3</sup> /h	2000
External Static Pressure		Rated	Pa	37
			InWg	0.15
		Range	Pa	0~150
			InWg	0~0.60
Fan Motor	Model		—	FG250B-ZL
	Drive Type		—	Direct
	Speed		rpm	1000/950/900/850
	Power Output		W	/
	Full Load Amp(FLA)		A	/
	Capacitor		uF	/
Fan	Type		—	Centrifugal
	Quantity		—	3
	Diameter-Height		inch	φ7.67-6.69
	Material		—	Inner Groove Copper Tube-Aluminum fin
	Face Area		sq.ft	3.77
			m <sup>2</sup>	0.35
	Pipe Diameter		mm	φ7.94

Evaporator	Number of rows	—	3
	Tube pitch(a)x row pitch(b)	mm	22×19.05
	Fins per Inch(FPI)	—	18
	Fin type	—	hydrophilic-window
	Number of circuits	—	7
	Length(L) x Height(H) x Width(W)	mm	1152×308×57.15
Operation temp		Cooling	°C ≥16
		Heating	°C ≤30
Drainage Connection Size(Outer Diameter×Wall Thickness)		mm	φ26×2.5
System Operation Control		—	Wired Controller
Dimension	Outline dimension (W×D×H)	mm	1400×700×300
	Package dimension (L×W×H)	mm	1601×813×365
Weight	Net Weight	kg	54.0
	Gross Weight	kg	60.0
Loading quantity (within panel)		20'GP	42
		40'GP	84
		40'HQ	98
Panel	Outline dimension (W×D×H)	mm	/
	Package dimension (W×D×H)	mm	/
	Net Weight	kg	/
	Gross Weight	kg	/
<b>Note:</b>			
1. The cooling capacity stated above is measured under following conditions : Indoor Condition: 27°C (81°F) DB/19°C (66.6°F) WB; Outdoor Condition: 35°C (95.4°F) DB/24°C (75.6°F) WB.			
2. Noise is tested in the semi-anechoic room, so it should be slightly higher in the actual Operation due to environmental change.			
3."1" is tested under standard condition: (请注明标准工况 ) "2" is tested under rated condition according to CE/Eurovent			
4.* Fan different speed			

